



**CELLULAR
CONCRETE LLC**
MEARLCRETE® DIVISION

INSULATING HOTEL FLOOR PROJECT IN USA



Ready Mix Filling Pump Hopper



CLC Pump



Self Leveling CLC Floor Insulation



Screeding



Finishing



Finishers "Shoes"



1000m² of Floor Finished in 1 Day

Underwriters Laboratories, Inc. Fire Rating Listings

- Design No. L501 - 1 hour fire rating - wood joists, 2 x 10" spaced 16", fire-stopped
- Design No. L502 - 1 hour fire rating - wood joists, 2 x 10" spaced 16",
fire- stopped furring channel-resilient, spaced 24"
- Design No. L512 - 1 hour fire rating - wood joists, 2 x 10" spaced 16", fire-stopped
- Design No. L513 - 1 hour fire rating - wood joists, nominal 2 x 10" spaced 24",
fire-stopped, furring channel-resilient.
- Design No L514 - 1 hour fire rating - wood joists, 2 x 10" spaced 16",
fire-stopped, furring channels-resilient
- Design No. L528 - 1 hour fire rating - wood frame/floor truss,
furring channels spaced 24"